



1

**GOVERNMENT OF ODISHA
PANCHYAT RAJ & DRINKING WATER DEPARTMENT
BHUBANESWAR**

**OFFICE OF THE BLOCK DEVELOPMENT OFFICER
BEGUNIAPADA BLOCK, GANJAM**

DETAIL TENDER CALL NOTICE (DTCN)

**“Construction of Sub-Centre Building at Sandhamula”
Tender Amount – Rs. 34,22,541/- (Approximate)**


**COST OF TENDER DOCUMENT: - Rs.6000=00
(NON- REFUNDABLE)**

PANCHYAT RAJ DEPARTMENT, ODISHA, BHUBANESWAR

TENDER FOR "Construction of Sub-Centre Building at Sandhamula"

	Tender Call Notice No. Identification No.	03 OF 2022-23 Date 14.02.2023 of Block Development Officer ,Beguniapada Block
2	Cost of Tender Schedule.	Rs: 6000/- (Rupees Ten thousand) only. (Non- refundable)
3	Last Date of Sale of Tender Schedule	From 16.2.2023 to 02.03.2023 up to 5:00 P.M in website https://ganjam.nic.in
4.	Date of receipt of tender	From 16.2.2023 to 02.03.2023 . (Excluding holyday) along with D.D of Rs.6000/-(Non-refundable) through RP/Speed Post to Office of the Block Development Office, Beguniapada Block.
5.	Date of opening of tender	At 11.00 A.M. on 03.03.2023 in the Office of the Block Development Office,Beguniapada Block.

Money Receipt No. _____ // Dt.


Block Development Officer,
Beguniapada, Ganjam.

N.B. : - This shall be submitted along with the tender documents in complete shape.



3

OFFICE OF THE PANCHAYATA SAMITI, BEGUNIAPADA, GANJAM.
DETAILED TENDER CALL NOTICE 03/22-23 date 14.02.2023

The Block Development Officer, Beguniapada on behalf of Governor of Odisha invite percentage rate bid in sealed cover system in confirming with detailed Tender Call Notice (D.T.C.N) from the registered Contractor of State P.W.D or equivalent class of CPWD/ Railways / MES/ Central Govt/ State Govt undertakings for the following works to be eventually drawn up in the PWD form (P.1). The Bid document can be obtained from the Office of the Panchayat Samiti, Beguniapada, Ganjam from 16-02-2023 to 02-03-2023 up to 5.00 PM (Excluding govt. Holydays) on payment of the cost of bid document in shape of A/c pay D.D/Bankers Cheque (Non-refundable) drawn in favour of Block Development Officer, Beguniapada, Ganjam payable at Indian Bank, Kanchana. The bid document can also be downloaded from official website of Ganjam District <https://www.ganjam.nic.in> In case of downloaded bid document cost of the bid document should be attached with bid. The tender shall be received through Register Post / Speed post in all working days from 16-02-2023 to 02-03-2023. The tender will be opened in office of the Block Development Officer, Beguniapada on 03-03-2023 at 11.00 AM in presence of tenderer or their authorized representative. The tender must be accompanied by EMD, attested copy of valid ITCC, PAN Card, GST clearance certificate, Valid License certificate & affidavit otherwise tender is liable for rejection. The envelope containing bid document and other necessary papers should be super scribed with "Tender Call Notice No.03/22-23/dated 14-02-2023"

Sl. No	Name of the work	Approx. Estimate cost.(in Rs)	Class of Contractor	Cost of tender Paper (in Rs.)(Non Refundable)	EMD 1% (in Rs)	Period of completion
1	Construction of Sub Centre Building at Sandhamula	34,22,541/-	"B" & "C"	6000/-	34,225/-	9(Nine) Calendar months
2	Construction of Guest House at Block premises, Beguniapada	19,80,475/-	"C" & "D"	6000/-	19,805/-	6(Six)Calendar months

2. The EMD / BID security will be executed as per office Memorandum No -5984 Dated 27/04/2021 as per provision made by the Govt of India in rule-171 of General Finance Rule 2017.
3. The work is to be completed within the stipulated time period.
4. Authority is reserved to reject any or all the tenders without assigning any reason thereof.
5. Each tender may take the form of definite rate for each item of work to be included in the contract and tenders containing in definite terms such as at estimated cost or schedule of rates or in percentage basis will not be considered. No conditional tender will be considered.
6. All rates in the tender is for finished items of work including all leads and lift of materials and tools and plants etc. Unless and otherwise as mentioned in the tender notice.
7. All taxes, fees, royalties etc. payable under the local rules including GST, Income Tax will be paid by the Contractor.
8. The Contractors should abide by the fair wages clause introduced by the Govt. and shall not less than fair wages fixed by the Govt. to the laborer engaged by him on the work.
9. The tender will not be considered unless the tenderer encloses the certified copy of the Income Tax clearance certificate, I.T. PAN Card, GST clearance certificate along with his tender and the original certificate is to be produced before the office at the time of opening the tender.
10. The percentage quoted in the tender should be written both in words and figures and in case of any discrepancies the unit and rate in words will prevail.
11. Extra items of work beyond the tender will not be paid.
12. All the material required for the work shall be supplied by the Contractor inclusive of cost, conveyance, royalty and taxes of materials.
13. On no account the work should be sublet to any body without prior approval of competent authority and in such cases the contract will be rescinded.
14. The Contractor shall be liable to fully indemnify the department for the payment of any compensation under workman compensation act VIII of 1962 on account of workman employed by the Contractor and the full amount of compensation payable will be recovered from the Contractor.
15. The right is reserved to make such increase and decrease in the quantities of items of work mentioned in the schedule attached to the tender notice which may be considered necessary for satisfactory completion of the work such change will not invalidate the contract rates. The contractor will not be entitled to any compensation on this account except to an extent of asking the extension of time where consider necessary.

Signature of Contractor

Block Development Officer
Beguniapada

35
Security
the success

4

16. The tenderer, whose tender is accepted shall forthwith upon written intimation being given to him for acceptance of his tender. The initial security deposit will be obtained as per the O.M No-5984 date -27/04/2021 of the works department. Thereafter the tenderer will sign the agreement in PWD form No. P-1. If he fails to enter into the required agreement within stipulated time, the result for the action as deem fit.
17. The earnest money of the unsuccessful tenders if given will be refunded on application of the tenderer or after the tender is finally decided.
18. In the event of dispute arises in tender contract, neither the Contractor nor the department shall have the right to bring a suit in any court of law situated outside the state of Orissa.
19. The work may be split up and distributed among several contractors if considered necessary. On the exigency of that circumstances of the work and the contractor is not entitled to any complaint on this accounts.
20. No compensation for any damage caused by the rains by similar action during the execution of work will be paid.
21. Letters found in the tender box intimating modification to the tender already given will not be entertained.
22. The Contractor shall made at his own cost housing accommodation and medical facilities for the labour engaged on the work.
23. The Contractor shall make arrangements at his own cost at work site for the proper storage of the materials made over to him till the work is completed and balance materials are returned to department if supplied by the department.
24. The tender which is not in prescribed proforma and not strictly according to the terms and conditions of the tender and specification is liable to rejection.
25. In case of delay in supply of departmental materials (whenever required) no compensation will be admissible but extension of time will be allowed.
26. Security deposit will be refunded six months after the work is completed and after payment of final bill.
27. The tenderer should produce copy of duplicate valid contractor license registered under appropriate authority along with tenders failing which the tender is liable for rejection.
28. The works will be executed as per the State PWD and BIS specification.
29. Except where otherwise provided in the contract will questions and disputes at the meaning of specifications designs, drawing and instructions herein before mentioned and as to the quality and workmanship materials used on the work or as to any other question, claim right matter of there what so ever in any assign out of or relates to contract designs, drawings, specifications, estimates, instructions, orders these conditions or otherwise concerning the works or the work of the executions failure to execute the same. Whether arising during the progress of the works, or after the completion.
30. No item of work should be done unless agreement is executed for the same. No payment shall be made if any work is done prior to execution of agreement for the items of work in question under the impression whether rightly or wrongly that the items of work for which agreement has already been executed.
31. Dewatering during execution if required to be paid by the contractor.
32. If any telephone cable or electric cable comes inside the trench alignment, the same should be intimated to the Engineer in charge at site and the contractor shall not claim for delay in shifting of the cable by the concerned departments.
33. Sufficient labourer should be engaged for removal of rock and it should be completed within time.
34. Exemption of EMD to the Engineer contractor will be allowed for a maximum of three works in a financial year and the fact of awarding a work with Exemption of EMD should be entered in the Original Registration Certificate of the Engineer Contractor. Engineer contractor desirous to avail the exemption of E.M.D/ISD. is required to submit an affidavit to the effect that he/she has not yet availed the facility for more than two works during the current financial year.

Signature of Contractor


Block Development Officer
Beguniapada

35. In pursuance to the Govt. of Odisha Works Dept. Office Memorandum No. 4559 Dt- 05.04.2021, Additional Performance Security shall be obtained from the bidder when the bid amount is less than the estimated cost put to tender. In such an event, only the successful bidder who has quoted less bid price / rates than the estimated cost put to tender shall have to furnish the APS in the rates as noted below.

Sl. No.	Range of Difference between the estimated cost put to tender and Bid amount.	Additional Performance Security to be deposited by the successful bidder.
1	Below 5%	No Additional Performance security
2	From 5% and above and below 10%	50% of (Difference between estimated cost put to tender and Bid Amount)
3	From 10% and above	150% of (Difference between estimated cost put to tender and Bid Amount)

Exact amount of Additional Performance Security (APS) in shape of Term Deposit Receipt pledged in favor of Block Development Officer, Beguniapada/ Bank Guarantee in favour of the Block Development Officer, Beguniapada from any Nationalized / Scheduled Bank in India counter guaranteed by its local branch at Bhubaneswar will be communicated through Letter of acceptance (LoA). After getting of (LoA) the successful bidder will produce the APS within 7 days of issue of letter of acceptance (LoA) by the Block Development Officer Beguniapada. If he/she fails, the bid shall be cancelled & he/she will be suspended for the time specified in the tender document. Further, proceeding for blacklisting shall be initiated against the bidder. If the APS is submitted in shape of Bank Guarantee by the bidder, then the validity of the Bank Guarantee should be for a minimum period equal to the period allowed for completion of the work plus defect liability period of one year and one month extra for transaction period

36. Bid must be accompanied with scanned copies of valid Registration Certificate duly registered in CDMS portal, active GSTIN, PAN Card and Affidavit in support of their claim along with their bid failing which the bid will be rejected. Bidders registered as "Engineer Contractors" desirous to avail exemption of E.M.D for participating in bid shall have to produce an affidavit for not having availed this facility in three works during the year 2021-22. In such case, the successful Engineer Contractor has to produce the original Registration Certificate for recording the fact of availing exemption of E.M.D & ISD. for award of the work. Bidders registered as S.C. & S.T. Contractors desiring to avail concession(s) / price preference as per prevailing rules should upload necessary document and affidavit in support of their claim along with their bid, failing which their case may not be considered for availing price preference as per the above rule. No claim in this regard after opening of the bid will be entertained.

37. In case, if lottery is inevitable for finalization of the tender, then the tender accepting authority will finalize the tender through a transparent lottery system, which will be held in the office of the Block Development Officer, Beguniapada, Dist:- Ganjam . The date and time of the lottery will be intimated to the qualified bidders through their address given and Email ID/WhatsApp including office notice board.

38. The Block Development Officer, Beguniapada, Dist:- Ganjam may be contacted during office hours on any working days for any further clarification between 10:00 A.M to 5.00P.M.

Signature of Contractor


Block Development Officer,
Beguniapada

GENERAL SPECIFICATION

1. The tender should include supply of all materials, labour, tools and plants centering, shuttering, scaffolding etc. complete unless otherwise specified.
2. All materials other than Government supplied will have to be of approved quality. The decision of the Executive Engineer on this issue will be final.
3. All exposed iron work shall be painted two coat of priming by paints whose quality a shade has to be approved by the Executive Engineer.
4. Plastering on RCC work shall not be paid for, if done by the Contractor.
5. Before issue of the departmental materials to the Contractor shall furnish bank guarantee of any of the nationalized banks for a sum equal to the cost of the materials. The bank guarantee shall be valid for the entire period of the agreement. The same will be refunded to the Contractor only after , the materials supplied to him are fully utilized in the works and amount thereof recovered from his bills in full or if the materials are partly utilized , the un utilized materials are returned by him to the department in full and in good condition and receipt thereof duly acknowledged to the concerned departmental office.

SPECIAL CLAUSE

- a All stock and store materials like cement, steel, Maxphalt paints etc. are to be arranged and supplied by the contractor himself as per IS specification subjected to approval quality by the Engineer-in-charge.
- b No monetary claim or compensation of any kind what so ever will be entertained by the Department nor this can be termed as a plea by the Contractor to apply for extension of time to complete the work (This has been given effect from 01-04-1996

The machineries as and when required for execution of work should normally be arranged and supplied by the Contractor himself.
- c. No cement will be supplied by the department and the contractor has to procure cement of approved quality as specified in the agreement at his own arrangements and produce the cash vouchers in support there of in token of actual transaction without scope for reimbursement of extra cost involved if any.
- d. Payment will be made on receipt of bills in complete shape by the authority subject to availability of funds (Letter of Credit) under respective head of account. The department will not be liable for payment of any compensation for delay in payment of running / final bill. Non payment of bills due to contingency if any, during the course of execution of works shall not be treated as a bar for suspending the work.
- e. The work is to be completed within the stipulated period .

Signature of Contractor



Block Development Officer,
Beguniapada, Ganjam.

(7)

SECTION – 8
FORMS

AFFIDAVIT

I, Sri Aged years Son/ Daughter / Wife of Sri
..... at present residing at PO P.S.
Dist, Pin Do hereby solemnly affirm as follows.

- i. That, I possess a valid license for Execution of works contract issued by *..... Belongs to
..... Class & is valid up to **.....
- ii. I am submitting tenders before the Block Development Officer, Beguniapada for execution of the
work *** " Construction of Sub-Centre at Building at sandhamula " in response to Tender Call
Notice No.03/ 2022-23, Date. 07.2.2023
- iii. I am swearing this affidavit that all tender documents and accompanying papers along with D.D (Non-
refundable) those being submitted by me before the **Block Development Officer, Beguniapada** are all
authentic and bonafied documents in the eyes of the law of the land.

That the facts stated in the affidavit are true to the best of my knowledge and belief.

Signature of Contractor

Note :

- * Mention the license issuing authority.
- ** Mention the date up to which the license is valid.
- *** Mention name of work for which tender is being submitted.

Block Development Officer
Beguniapada

PERFORMANCE RECORD OF CONTRACTOR

1. Name of the Contractor :
2. Registration No. and Date :
3. Class of Contractor :
4. Licensing Authority :
5. License valid up to :
6. Details of works executed :

Sl. No.	Jobs under execution	Agreement amount	Date of Commencement	Stipulated Date of Completion	Whether work is progressing as per programme	Reasons for delay, if any.
1	2	3	4	5	6	7

7. Whether the Contractor has requisite machineries & personnel deployed (details of machinery and personnel deployed) :
8. Whether the quality of construction is satisfactory :
9. Whether he has capability to make good the loss time :
10. Whether the Contractor has abandoned any work in the past three years, if yes, the details thereof. :
11. Whether the Contractor has entered in to any litigation in the past if yes, the details thereof. :

Name of the Certifying Officer
With official seal

Signature of Contractor


Block Development Officer
Beguniapada

Certificate of No relationship

I/We hereby certify that I/We am / are not related to any officer of P.W.D. of the rank of Asst. Engineer and above and any officer of the rank of Asst. Secretary and above in the P. R & D. W Dept. I/ We am/are aware that if the facts subsequently proved to be false my/our contract will be rescinded with for feature of EMD & security deposit and I/We shall be liable to make good the loss or damage resulting from such cancellation.

I/We also note that, non-submission of this certificate will render my/ our tender liable for rejection.

Signature of Contractor

Address _____

Date: _____


**Block Development Officer,
Beguniapada**

**INFORMATION REGARDING CURRENT LITIGATION DEBARRING EXPELLING
OF TENDERER OR ABANDONMENT OF WORK BY THE TENDERER.**

1. a) Is the tenderer currently involved in any litigation relating to the works. Yes/No
b) If yes, give details.
2. a) Has the tenderer or any of its constituent partners has been debarred / expelled by any agency in India during the last three years. Yes/No
3. a) Has the tenderer or any of its constituent partners failed to perform on any contract work in India during the last three years. Yes/No
b) If yes, give details :

Note:- If any information in this schedule is found to be incorrect or concealed, qualification application will be summarily be rejected.

Signature of Contractor

Address _____

Date: _____


Block Development Officer,
Beguniapada

FORM OF BID SECURITY DECLARATION

ANNEXURE-"V"

(Letter head of the Bidder)
(Date)

Name of the Work:-

Bid Id No. :-

To

The Block Development Officer,
Beguniapada

We, the undersigned, declare that:

1. We understand that, according to your conditions, bids must be supported by a Bid Security Declaration.
2. We accept that the Authority/Employer/Tender Inviting Authority shall cancel our empanelment and/or suspend/prohibit/debar/blacklist from participating in bidding in any contract of the state for a minimum period of 180 days, if we are in breach of our obligation(s) under the bid conditions, because we:
 - a. have withdrawn our Bid prior to the expiry date of the bid validity specified in the letter of Bid or any extended date provided by us: or
 - b. having been notified of the acceptance of our Bid by the Employer prior to the expiry date the bid validity in the letter of Bid or any extended date provided by us,
 - i) Fail or refuse to furnish the Performance Security and, Additional Performance Security, if required in accordance with the ITB/Terms of the Bid document/RFP, or
 - ii) Fail to agree to the decisions of the contract negotiation meeting or
 - iii) Fail or refuse to execute the contract.
3. We understand this Bid Security Declaration shall expiry if we are not the successful bidder upon the earlier of your notification of the name of the successful bidder through award of contract: or after the expiry date of the bid validity.

Name of the Bidder* _____

Name of the person duly authorized to sign the bid on behalf of the Bidder** _____

Title of the person signing the Bid _____

Signature of the person named above _____

Date signed _____ day of _____

*In the case of the Bid submitted by Joint venture specify the name of the Joint venture as Bidder

**Person signing the Bid shall have the power of attorney given by the Bidder attached to the Bid.

(Note. In case of a joint venture, the Bid Security Declaration must be in the name of all members to the Joint Venture that submits the Bid)


Block Development Officer,
Beguniapada

CHECK LIST (SUBMITTED OR NOT)

		Tick appropriate column			
		YES		NO	
1	Certificate of Registration of Contractor with enrolment in CDMS Portal-attached.	YES		NO	
2	Certified copy of power of attorney in case of partnership firm, limited or corporation attached.	YES		NO	
3	Bid security declaration furnished.	YES		NO	
4	Copy of PAN Card Furnished.	YES		NO	
5	Copy of GST number with related documents furnished.	YES		NO	
6	Affidavit for authenticity of documents, Bid security declaration in lieu of EMD & Bid information furnished.	YES		NO	
7	Cost of bid document + GST number with related documents	YES		NO	
8	List of Plant / Equipment Furnished	YES		NO	
9	No Relation Certificate	YES		NO	
10	Affidavit for during the year (for Engineering Contractors)	YES		NO	
11	No Litigation Certificate	YES		NO	
12	Any other document as per DTCN.	YES		NO	
a		YES		NO	
b		YES		NO	
c		YES		NO	


 Block Development Officer,
 Beguniapada

NAME OF THE PROJECT:- Construction of SC Building at Sandhamula under Begunlapada block

BILL OF QUANTITY

Sl. No.	Description of Items	Quantity	Unit	Rate (In Lakhs)	Amount (In Lakhs)
1	Earth Work in excavation of foundation in hard soil within initial leads of 50m & lifts of 1.5m including dressing and levelling of bed etc. and adding contractor's profit and over head charges, etc. complete in all respect.	106.32	Cum	195.37	20,771.74
2	Extra lifts of 1.50 mtr or part thereof over the initial lift of 1.5 mtr in all kinds of embankments and road works and ordinary earthwork in general.	3.21	Cum	210.74	676.48
3	Excavation of foundation in hard rock (granite) removed by chiselling including dressing and levelling the bed not exceeding 1.50 mtr. in depth and depositing the soil within initial lead of 50 mtr. and as per specification approved by the Department.	3.21	Cum	2,150.73	6,903.83
4	Supplying & filling of foundation with coarse sand well watered and rammed including cost, cost of all labour, carriage, royalty complete in all respect.	107.65	Cum	561.89	60,487.46
5	Cement Concrete (1:3:6) using 40mm size hard granite C.B. metal approved quality from approved quarry including cost, carriage, royalty, cost of all labour, etc complete and as directed by E.I.C.	26.48	Cum	4,697.64	1,24,393.51
6	Supplying all materials, labour, T&P and providing cement concrete (1:1.5:3) with 12mm size hard broken granite chips for R.C.C works including hoisting, laying, watering, curing, conveyance of all materials to worksite, payment of royalty, taxes etc all complete as per specification and direction of the E.I.C	1.04	Cum	6,728.00	6,997.12
7	Cement Concrete (1:2:4) using 12mm size hard granite C.B. chips approved quality from approved quarry including cost, carriage, royalty, cost of all labour, etc complete and as directed by E.I.C.	2.87	Cum	6,071.71	17,425.81
8	Random Rubble stone masonry in cm (1:6) in foundation & plinth using gh stones of app quality, including splays, cuttings, circular moldings, watering, curing, cost, conveyance, taxes, royalties of all materials & labour with T&P etc. complete in all respect.	34.33	Cum	3,367.50	1,15,606.28
9	R.C.C. M-20 grade with 20mm and down grade C.B. chips of approved quality from approved quarry including hoisting, laying hire charges of concrete mixture, vibrator, watering, curing and cost of all materials and labour, centering shuttering etc complete but excluding cost of reinforcement.				-
	A) COLUMN BASE FOOTING	14.35	Cum	5,061.17	72,627.79
	B) COLUMN SUPER STRUCTURE				-
	Ground Floor	4.25	Cum	10,962.65	46,591.26
	First Floor	2.93	Cum	12,261.19	35,925.28
	Second Floor	1.03	Cum	13,802.14	14,216.20
	C) PLINTH BAND	5.54	Cum	5,430.86	30,086.96
	D) LINTEL BAND				-

		2.47	Cum	8,734.81	21,574.98
		2.03	Cum	9,587.82	19,463.27
	Ground Floor				
	First Floor				
	(F) CHAJJA	18.37	Sqm	807.53	14,834.33
	Ground Floor	10.57	Sqm	910.92	9,628.42
	First Floor				
	F) BEAM	5.23	Cum	10,962.65	57,334.66
	Ground Floor	3.76	Cum	12,261.19	46,102.07
	First Floor				
	(G) STAIRCASE 2				
	Ground Floor	1.63	Cum	9,843.16	16,044.35
	First Floor	1.63	Cum	10,917.81	17,796.03
	(H) ROOF SLAB				
	Ground Floor	13.41	Cum	9,346.93	1,25,342.33
	First Floor	10.69	Cum	10,322.36	1,10,346.00
	Second Floor	2.03	Cum	11,475.54	23,295.34
10	Straightening, cutting, bending bent up or coiled rods, including cranking, hooking, welding or jointing the M.S. rods or tor conforming to I.S. 432 (Plain) and 1785 (Tor) steel and binding, tying the grills, hoisting, lowering and placing in proper position required for R.C.C. works including cost, conveyance and taxes of M.S. rods or tor steel and binding wires of 18 to 20 gauge and cost of all labour etc. complete in all respect.				
	Ground Floor	51.29	Qtl	8,714.35	4,46,959.01
	First Floor	25.32	Qtl	8,738.71	2,21,264.14
	Second Floor	3.17	Qtl	8,763.20	27,779.34
11	25mm thick CC 1:2:2 with 6mm size CB chips for grading concret over roof slab etc. complete.				
	Ground Floor	102.93	Sqm	299.73	30,851.21
	First Floor	85.55	Sqm	328.46	28,099.75
	Second Floor	20.35	Sqm	361.52	7,356.93
12	Fly Ash Brick work with Fly Ash Bricks of 23cm.x 11cm.x 8cm. size having crushing strength not less than 75 Kg/Cm ² in cement mortar (1:6) in superstructure including splays, cuttings, circular moldings, watering & curing for 7 days, cost, conveyance, taxes & royalties of all materials, labour with T&P etc. complete in all respect.				
	Sub structure	4.78	Cum	4,367.58	20,877.03
	Super structure				
	Ground Floor	36.18	Cum	4,405.90	1,59,405.46
	First Floor	34.23	Cum	4,679.13	1,60,166.69
	Second Floor	10.39	Cum	4,993.36	51,881.03
13	20mm thick C.P. With C.M. (1:6) over stone masonry with cost & conveyance of all materials, cost of all labour, etc complete.	19.50	Sqm	214.31	4,179.05
14	12mm thick C.P.(1:6) on brick masonry to the smooth surface including watering, curing, cost, carriage, royalty of all materials, cost of all labour, etc complete as per the direction of E.I.C.				
	Ground Floor	121.80	Sqm	142.98	17,414.96
	First Floor	110.72	Sqm	148.63	16,456.09
	Second Floor	67.11	Sqm	154.56	10,372.48
15	12 mm thick cement plaster (1:4) finished smooth to brick masonry with cement punning for skirting after racking out joints including watering, curing including cost, conveyance, taxes, royalties & labour with T&P etc. complete.	19.71	Sqm	161.73	3,188.35

16	Cement rule pointing including racking out joints (1:3) over brick work including watering, curing, cost, conveyance, taxes, royalties & labour with T&P etc. complete.	17.54	Sqm	166.70	2923.75
17	16mm thick C.P. (1:6) over brick masonry to the smooth surface including watering, curing cost, carriage, royalty, and taxes of all materials, cost of all labour, etc complete as per the direction of E.I.C.				
	Ground Floor				
	First Floor				
	Second Floor	349.30	Sqm	204.10	71,292.13
		274.01	Sqm	209.13	57,304.81
		37.65	Sqm	214.32	8,069.08
18	6 mm thick C.P. (1:4) to RCC surfaces finished smooth including closed deep chipping and slurry treatment, watering, curing cost, carriage & royalty of all materials, cost of all labour, etc complete as per the direction of E.I.C.				
	Ground Floor				
	First Floor	86.00	Sqm	158.88	13,663.68
		64.05	Sqm	162.82	10,428.62
19	Supplying, fitting & fixing of 10 mm thick & size of 600x600 mm Glazed Vitrified floor tiles (GVT) of matt finish(WOODEN FINISH/RUSTIC FINISH) with veilcraft (VC) shield(Scratch free/stain free) with water absorption limit between 0.08% to 3% and conforming to IS : 15622:2006 (Group B Ib) laid on 20 mm thick cement mortar (1:4) and filling joints with white cement of approved quality including cost of all materials, etc. required for the work all complete as per direction of E.I.C.				
	Ground Floor	86.00	Sqm	979.90	84,271.24
	First Floor	77.05	Sqm	988.65	76,175.34
20	Supplying, fitting & fixing of Chequered tiles laid on 20 mm thick cement mortar (1:4) and filling joints with white cement of approved quality including cost of all materials, etc. required for the work all complete as per direction of E.I.C.				
	Ground Floor	23.14	Sqm	575.11	13,308.00
	First Floor	7.64	Sqm	583.86	4,460.68
21	Fixing of 10 mm thick & size of 600x600 mm Glazed Vitrified wall tiles (GVT) of matt finish(WOODEN FINISH/RUSTIC FINISH) with veilcraft (VC) shield(Scratch free/stain free) with water absorption limit between 0.08% to 3% and conforming to IS : 15622:2006 (Group B Ib) in dados skirting and risers of steps on 12mm thick CP (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the tiles including cost, carriage, cost of all labour etc. complete.				
	Ground Floor	118.23	Sqm	1,076.23	1,27,242.67
	First Floor	58.38	Sqm	1,091.35	63,718.30
22	Priming 1 coat with wall primer water bond cement primer including all labour, materials etc. complete.				
	Ground Floor	458.37	Sqm	59.42	27,236.35
	First Floor				
	Outside	177.83	Sqm	61.93	11,013.01
	Inside	330.78	Sqm	60.91	20,147.87

23	Finishing wall surface with Cement based wall putty (water based) of approved make and finished smooth & even surface to receive painting including cost of scaffolding etc with cost of all materials, labour etc complete.					20,996.38
	Ground Floor	317.07	Sqm	66.22		26,439.32
	First Floor	330.78	Sqm	79.93		
24	Wall painting 2 coats with plastic emulsion paint of approved shade on new work to give an even shade including cost of paint etc complete.					24,994.63
	Ground Floor	317.07	Sqm	78.83		26,608.02
	First Floor	330.78	Sqm	80.44		
25	Wall painting two coat with any approved weather coat paint including cost of all materials, labour and I&P require for the work etc. complete as directed by the E.I.C.					
	Ground Floor	141.30	Sqm	73.18		10,340.33
	First Floor	177.83	Sqm	75.87		13,492.09
26	Supplying of M.S. Door, Window with grills, Grills made out of M.S. Angle frame, M.S. Flat, Sheet etc of approved section & design, electrically welded properly with all necessary locking arrangement, and 1 coat red oxide primer including cost of all materials, labour charges, carriage of materials to site etc. complete.					
	M S Double leaf Door	579.36	Kg	70.20		40,671.07
	MS Double leaf window with grill	43.23	Kg	67.97		2,938.65
	M S Grills	961.60	Kg	55.55		53,416.88
27	Labour for fitting & fixing of MS grills & shutters as per approved design including cost of all materials complete.	72.04	Sqm	68.07		4,903.76
28	Supplying, fitting & fixing of Un-plasticized Poly Vinyl Chloride (UPVC) (FENESTA/ NCL VEKA Ltd.) casement door-60-series duly manufactured using UPVC reinforced profiles of 60mm x 55 mm x 2.5mm for outer frames, 102mm x 60mm x 2.25mm for casement door Sash profile and 74mm x 60mm x 2.5mm mullion profile capable of mounting single glazing system, structurally reinforced with hot dip galvanized upto 50 microns of minimum thickness of 2.0mm prefabricated & welded through fusion welding the door sash shall be fitted with 12mm thick WPC Board of Greenply make duly fixed with EPDM weathering seal resistance accessories like clipping locking system made of aluminium 1-no. per set of sashes and the system is to be installed at the site using anchor fasteners, silicon rubber sealant, easy glazing at the site, etc including cost, conveyance of all materials, accessories, labour charges, materials & products conforming to ASTM-D-638-14, EN-477-95 and other applicable codes and standards.	12.48	Sqm	8,963.00		1,11,858.24

29	<p>Supplying, fitting & fixing of Un plasticized Poly Vinyl Chloride (UPVC) (FENESTA/ NCL VEKA Ltd.) three track -three panel sliding window-60-seies duly manufactured using UPVC reinforced profiles of 108mmx 45 mm x 2.5mm for outer frames and window Sash profile of 39mm x 58mm x 2.5mm capable of mounting single glazing system, structurally reinforced with hot dip galvanized upto 50 microns of minimum thickness of 1.5mm prefabricated & welded through fusion welding the window frame shall be fitted with 6mm thick clear toughened glass of SAINT GOBAIN make duly fixed with EPDM weathering seal resistance and the system is to be installed at the site using reinforced large coupler at the site using anchor fasteners, silicon rubber sealant, easy glazing/ deglazing at the site etc including cost and conveyance of all materials, accessories, labour charges, material & products confirming to ASTM-D-638-14, EN-477-95 and other applicable codes and standards.</p>	25.09	Sqm	5,984.00	1,50,138.56
30	<p>Providing, fitting, fixing up partition walling OEL aluminium anodized section No. 9210 and 9207 as single groove and double groove respectively as horizontal and vertical member and OEL section 4660 as Tapered clip for fixing up 6mm thick Black glass and jointing angle No. 1855 including all fitting ,cost of all materials, taxes, labour, T&P etc. complete as per direction of Engineer in Charge.</p>	5.57	Sqm	3,668.71	20,434.71
31	<p>Supplying, fitting & fixing of Un-plasticized Poly Vinyl Chloride (UPVC) (FENESTA/ NCL VEKA Ltd.) ventilator/ Top hung-60-seies duly manufactured using UPVC reinforced profiles of 60mmx 55 mm x 2.5mm for outer frames, 75mm x 60mm x 2.25mm for casement window sash profile capable of mounting single glazing system, structurally reinforced with hot dip galvanized upto 50 microns of minimum thickness of 1.5mm prefabricated & welded through fusion welding and window frame shall be fitted with 6mm thick cleared thoughtened glass of SAINT-GOBAIN make duly fixed with EPDM weathering seal resistance accessories like clipping locking system made up of aluminium 1 No. per set of sashes and the system is to be installed at the site using anchor fasteners, silicon rubber sealant, easy glazing/ deglazing at site etc including cost and conveyance of all materials, accessories, labour charges, materials & products confirming to ASTM-D-638-14, EN-477-95 and other applicable codes and standards.</p>	1.37	Sqm	7,115.00	9,747.55
32	<p>Supplying, fitting and fixing of stainless steel of 304 grade in hand railing using 50 mm dia of 2 mm thick circular pipe with Balustrade of size 32 mm x 32mm x 2mm @ 0.90 mtr C/C and stainless aquare pipe bracing of size case as per approved design and specification, buffing, polishing etc. with the cost, conveyance taxes of all material, cost of all labour etc. complete in all respect.</p>	10.00	Rmt	3,506.51	35,065.10

33	Priming one coat with any approved primer including cost of primer & labour to give an even shade excluding cost of primer.	79.17	Sqm	55.62	4,403.44
34	Painting two coats with approved enamel paints of approved colour, shade over a coat of primer including sand papering, polishing the surface, cost, conveyances of all materials and cost of all labour etc, complete as per specification & direction of E.I.C.	79.17	Sqm	138.28	10,947.63
35	Supplying all materials, labour, T&P and constructing inspection chamber of the following size with cement concrete(1:3:6) using 40mm size hard granite metal on bed, Flyash brickwork in cement mortar(1:6), moulding and shaping the channel inside and benching with cement concrete (1:2:4) using 12mm size h.g chips, 12mm thick cement plaster (1:4) with punning to inside, cement flush pointing (1:3) to outside, R.C.C cover slab in (1:2:4) using 12mm size h.g chips with RCC man hole cover, earthwork in excavation in all kinds of soil and refilling the cavity around the chamber including watering, curing, conveyance of all materials to worksite, payment of royalty, taxes etc all complete as per approved specification and direction of the Engineer in charge	1.00	Each	7,845.80	7,845.80
36	Supplying all materials, labour, T&P and constructing soakway pit of the following size with dry brick walling from bottom upto invert of inlet pipe and Flyash brickwork in cement mortar (1:6) for the remaining height at top, cement concrete (1:4:8) using 40mm size hg chips on bed, 12mm thick cement plaster (1:4) inside and outside over masonry brickwork, gravel backing in the rear of well steining, RCC cover slab in cement concrete (1:2:4) using 12mm size hg chips fitted with iron lifting handles including earthwork in open well excavation in all kinds of soil and refilling of cavity around the pit & painting the iron works, watering, curing, conveyance of all materials to worksite, payment of royalty, taxes etc all complete as per approved specification and direction of the Engineer in charge	1.00	Each	13,646.00	13,646.00

37	Supplying all materials,labour,T&P and fixing Rotational moulded polyethylene cylindrical vertical water storage tanks conforming to IS : 12701-1996 including cutting holes through the tank and fixing mild steel tubes and fittings and providing extra sockets and jam nuts, fixing ball valve etc. including hoisting upto a height of 5 metres above ground level and placing the tank to the required position and providing Flyash brickwork in cement mortar (1:6) of 0.46m height in staging and in circular protection wall to support the tank, 12mm thick cement plaster (1:6) over brickwork, R.C.C slab of size 1.60mx1.60m and 0.10m thick, R.C.C beam of 0.25mx0.30m and 2.60m average length in cement concrete(1:2:4) using 12mm size h.g chips including centering and shuttering, watering, curing, conveyance of all materials to worksite etc all complete as per specification and direction of the Engineer in charge	1.00	Each	21,674.65	21,674.65
TOTAL (In Lakhs)					34,22,541.36

Limited to Rs **34,22,541.00**

Total 37 (Thirty Seven) Items Only (Rupees Thirty four Lakhs Twenty two thousand five Hundred forty one only)


 Junior Engineer
 NHM, Ganjam


 Assistant Executive Engineer
 Beguniapada


 Block Development Officer
 Beguniapada

My /our quoted rate is.....% (Both in figures & Words) excess over/ less than/equal to the above estimated cost.

Signature of Tenderer