



OFFICE OF THE PANCHAYAT SAMITI, BEGUNIAPADA, GANJAM.

DETAILED TENDER CALL NOTICE No02/23-24 /Date. 02.9.2023

Letter No 3425

/Date 02/09/2023

The Block Development Officer, Beguniapada on behalf of Governor of Odisha invites percentage rate bid in sealed cover system in confirming with detailed Tender Call Notice (D.T.C.N) from the registered Contractor of State P.W.D or equivalent class of CPWD/ Railways / MES/ Central Govt./ State Govt undertakings for the following works to be eventually drawn up in the PWD form (P.1). The Bid document can be obtained from the Office of the Panchayat Samiti, Beguniapada, Ganjam from 03.9.2023 to 10.9.2023 up to 5.00 PM (Excluding govt. Holydays) on payment of the cost of bid document in shape of A/c pay D.D/Bankers Cheque (Non-refundable) drawn in favour of Block Development Officer, Beguniapada, Ganjam payable at Indian Bank, Kanchana .The bid document can also be downloaded from official website of Ganjam District <https://www.ganjam.nic.in> In case of download bid document, cost of the bid document in the above form should be attached with bid. The tender shall be received through Register Post / Speed post on all working days from 03.9.2023 to 10.9.2023 up to 5.00 PM (Excluding govt. Holydays).The tender will be opened in office of the Block Development Office, Beguniapada on 11.9.2023 at 11.00 AM in presence of tenderer or their authorised representative. The tender must be accompanied by EMD, attested copy of valid ITCC, PAN Card, GST clearance certificate, Valid Licence certificate& affidavit otherwise tender is liable for rejection. The envelope containing bid document and other necessary papers should be super scribed with "Tender Call Notice No.02/23-24/dated 02.9.2023. The undersigned reserves the right to negotiate or reject any or all the tenders in the interest of govt. without assigning any reason thereof. The other terms & conditions are available in tender document/paper.

Sl. No	Name of the work	Approx. Estimate cost.(in Rs)	Class of Contract or	Cost of tender Paper (inRs.)(Non Refundable)	EMD 1% (in Rs)	Period of completion
1	Renovation &Construction of CHC Kodala under 5t Transformation	60,42,900/-	"B"	10000/-	60,429/-	9(Nine) Calendar months

Memo No 3426

Block Development Officer,
Beguniapada

Date 02/09/2023

Copy in duplicate submitted to Deputy Director(Advt) / Deputy Secretary toGovt., Information and public Relation Deptt.Odisha , BBSR for favour of kin information . it is requested to publish the notice in one edition of two different widely published leading local Odia daily and English newspaper before 27-03-2023

Memo No 3427

Block Development Officer,
Beguniapada

Date 02/09/2023

Copy submitted to Collector & District Magistrate, Ganjam /Chief Development Officer-cum-EO, Zilla Parishad, Ganjam /DEO, Ganjam for favour of Kind information.

Memo No 3428

Block Development Officer,
Beguniapada

Date 02/09/2023

Copy forwarded to Executive Engineer RWD, Ganjm/Executive Engineer , R & B, Ganjam /Executive Engineer, Irrigation division , Ganjam for favour of Kind information & wide publication

Block Development Officer,
Beguniapada

Memo No 3429

Date 02/09/2023

Copy submitted to Deputy Secretary to Govt. , PR & DW Deptt, Odisha , BBSR for favour of Kind information .


Block Development Officer,
Beguniapada

Memo No 3430

Date 02/09/2023

Copy forwarded to All Tahasildars/ All Block Development Officers of Ganjam District /Executive Officer, NAC, Kodala / BEO, Beguniapada for favour of Kind information & wide publication


Block Development Officer,
Beguniapada

Memo No 3431

Date 09/09/2023

Copy to DIONIC, Ganjam for information. He is requested to publish the notice in the District web site <https://www.ganjam.nic.in>.

Copy to Notice Board, Panchayat Samiti, Beguniapada for information of general public.


Block Development Officer,
Beguniapada



GOVERNMENT OF ODISHA
PANCHYAT RAJ & DRINKING WATER DEPARTMENT
BHUBANESWAR

OFFICE OF THE BLOCK DEVELOPMENT OFFICER
BEGUNIAPADA BLOCK, GANJAM

DETAIL TENDER CALL NOTICE (DTCN)

“Renovation & Construction of CHC, Kodala , Beguniapada”
Tender Amount – Rs. 60,42,900/- (Approximate)

COST OF TENDER DOCUMENT: - Rs.10000=00
(NON- REFUNDABLE)

PANCHYAT RAJ DEPARTMENT, ODISHA, BHUBANESWAR

TENDER FOR "Renovation & Construction of CHC, Kodala

	Tender Call Notice No. Identification No.	02 OF 2023-24 Dnto 02.09.2023 of Block Development Officer ,Beguniapada Block
2	Cost of Tender Schedule.	Rs: 10000/- (Rupees Ten thousand) only. (Non- refundable)
3	Last Date of Sale of Tender Schedule	From 03.09.2023 to 10.09.2023 up to 5:00 P.M in website https://ganjam.nic.in excluding Govt holiday.
4.	Date of receipt of tender	From 03.09.2023 to 10.09.2023 up to 5:00 P.M (Excluding holyday) along with D.D of Rs.10000/- (Non-refundable) through RP/Speed Post to Office of the Block Development Office, Beguniapada Block.
5.	Date of opening of tender	At 11.00 A.M. 11.09.2023 in the Office of the Block Development Office, Beguniapada Block.

Money Receipt No. _____ // Dt.


Block Development Officer,
Beguniapada, Ganjam.

N.B. : - This shall be submitted along with the tender documents in complete shape.



OFFICE OF THE PANCHAYAT SAMITI, BEGUNIAPADA, GANJAM.

DETAILED TENDER CALL NOTICE No 02/23-24 Date. 02.09.2023

The Block Development Officer, Beguniapada on behalf of Governor of Odisha invites percentage rate bid in sealed cover system in confirming with detailed Tender Call Notice (D.T.C.N) from the registered Contractor of State P.W.D or equivalent class of CPWD/ Railways / MES/ Central Govt./ State Govt undertakings for the following works to be eventually drawn up in the PWD form (P.1). The Bid document can be obtained from the Office of the Panchayat Samiti, Beguniapada, Ganjam from 03.9.2023 to 10.9.2023 up to 5.00 PM (Excluding govt. Holydays) on payment of the cost of bid document in shape of A/c pay D.D/Bankers Cheque (Non-refundable) drawn in favour of Block Development Officer, Beguniapada, Ganjam payable at Indian Bank, Kanchana. The bid document can also be downloaded from official website of Ganjam District <https://www.ganjam.nic.in> In case of download bid document, cost of the bid document in the above form should be attached with bid. The tender shall be received through Register Post / Speed post on all working days from 03.9.2023 to 10.9.2023 up to 5.00 PM (Excluding govt. Holydays). The tender will be opened in office of the Block Development Office, Beguniapada on 11.9.2023 at 11.00 AM in presence of tenderer or their authorised representative. The tender must be accompanied by EMD, attested copy of valid ITCC, PAN Card, GST clearance certificate, Valid Licence certificate & affidavit otherwise tender is liable for rejection. The envelope containing bid document and other necessary papers should be super scribed with "Tender Call Notice No.02/23-24/dated 02.9.2023. The undersigned reserves the right to negotiate or reject any or all the tenders in the interest of govt. without assigning any reason thereof. The other terms & conditions are available in tender document/paper.

Sl. No	Name of the work	Approx. Estimate cost.(in Rs)	Class of Contract or	Cost of tender Paper (inRs.)(Non Refundable)	EMD 1% (in Rs)	Period of completion
1	Renovation & Construction of CHC Kodala under 5t Transformation	60,42,900/-	"B"	10000/-	60,429/-	9(Nine) Calendar months

- The EMD will be executed as per office Memorandum No -5984 Dated 27/04/2021 as per provision made by the Govt of India in rule-171 of General Finance Rule 2017.
- The work is to be completed within the stipulated time period.
- Authority is reserved to reject any or all the tenders without assigning any reason thereof.
- Each tender may take the form of definite rate for each item of work to be included in the contract and tenders containing in definite terms such as at estimated cost or schedule of rates or in percentage basis will not be considered. No conditional tender will be considered.
- All rates in the tender is for finished items of work including all leads and lift of materials and tools and plants etc. Unless and otherwise as mentioned in the tender notice.
- All taxes, fees, royalties etc. payable under the local rules including GST, Income Tax will be paid by the Contractor.
- The Contractors should abide by the fair wages clause introduced by the Govt. and shall not less than fair wages fixed by the Govt. to the laborer engaged by him on the work.
- The tender will not be considered unless the tenderer encloses the certified copy of the Income Tax clearance certificate, I.T. PAN Card, GST clearance certificate along with his tender and the original certificate is to be produced before the office at the time of opening the tender.
- The percentage quoted in the tender should be written both in words and figures and in case of any discrepancies the unit and rate in words will prevail.
- Extra items of work beyond the tender will not be paid.

Signature of Contractor


Block Development Officer
Beguniapada

12. All the material required for the work shall be supplied by the Contractor inclusive of cost, conveyance, royalty and taxes of materials.
13. On no account the work should be sublet to any body without prior approval of competent authority and in such cases the contract will be rescinded.
14. The Contractor shall be liable to fully indemnify the department for the payment of any compensation under workman compensation act VIII of 1962 on account of workman employed by the Contractor and the full amount of compensation payable will be recovered from the Contractor.
15. The right is reserved to make such increase and decrease in the quantities of items of work mentioned in the schedule attached to the tender notice which may be considered necessary for satisfactory completion of the work such change will not invalidate the contract rates. The contractor will not be entitled to any compensation on this account except to an extent of asking the extension of time where consider necessar
16. The tenderer, whose tender is accepted shall forthwith upon written intimation being given to him for acceptance of his tender. The initial security deposit will be obtained as per the O.M No-5984 date -27/04/2021 of the works department. There after he will sign the agreement in PWD form No. P-1. If he fails to enter into the required agreement within stipulated time shall result for the action as deem fit.
17. The earnest money of the unsuccessful tenders if given will be refunded on application of the tenderer or after the tender is finally decided
18. In the event of dispute arises in tender/contract, neither the Contractor nor the department shall have the right to bring a suit in any court of law situated outside the state of Orissa.
19. The work may be split up and distributed among several contractors if considered necessary. On the exigency of that circumstances of the work and the contractor is not entitled to any complaint on this accounts.
20. No compensation for any damage caused by the rains by similar action during the execution of work will be paid.
21. Letters found in the tender box intimating modification to the tender already given will not be entertained.
22. The Contractor shall made at his own cost housing accommodation and medical facilities for the labour engaged on the work.
23. The Contractor shall make arrangements at his own cost at work site for the proper storage of the materials made over to him till the work is completed and balance materials are returned to department if supplied by the department.
24. The tender which is not in prescribed proforma and not strictly according to the terms and conditions of the tender and specification is liable to rejection.
25. In case of delay in supply of departmental materials (whenever required) no compensation will be admissible but extension of time will be allowed.
26. Security deposit will be refunded six months after the work is completed and after payment of final bill.
27. The tenderer should produce copy of duplicate valid contractor license registered under appropriate authority along with tenders failing which the tender is liable for rejection.
28. The works will be executed as per the State PWD and BIS specification.
29. Except where otherwise provided in the contract will questions and disputes at the meaning of specifications designs, drawing and instructions herein before mentioned and as to the quality and workmanship materials used on the work or as to any other question, claim right matter of there what so ever in any assign out of or relates to contract designs, drawings, specifications, estimates, instructions, orders these conditions or otherwise concerning the works or the work of the executions failure to execute the same. Whether arising during the progress of the works, or after the completion.
30. No item of work should be done unless agreement is executed for the same. No payment shall be made if any work is done prior to execution of agreement for the items of work in question under the impression whether rightly or wrongly that the items of work for which agreement has already been executed.
31. Dewatering during execution if required to be paid by the contractor.
32. If any telephone cable or electric cable comes inside the trench alignment, the same should be intimated to the Engineer in charge at site and the contractor shall not claim for delay in shifting of the cable by the concerned department.
33. Sufficient labourer should be engaged for removal of rock and it should be completed within time.

Signature of Contractor


Block Development Officer
Beguniapada

34. Exemption of EMD to the Engineer contractor will be allowed for a maximum of three works in a financial year and the fact of awarding a work with Exemption of EMD should be entered in the Original Registration Certificate of the Engineer Contractor. Engineer contractor desirous to avail the exemption of E.M.D/ISD, is required to submit an affidavit to the effect that he/she has not yet availed the facility for more than two works during the current financial year.

35. In pursuance to the Govt. of Odisha Works Dept. Office Memorandum No. 4559 Dt:- 05.04.2021, Additional Performance Security shall be obtained from the bidder when the bid amount is less than the estimated cost put to tender. In such an event, only the successful bidder who has quoted less bid price / rates than the estimated cost put to tender shall have to furnish the APS in the rates as noted below.

Sl. No.	Range of Difference between the estimated cost put to tender and Bid amount.	Additional Performance Security to be deposited by the successful bidder.
1	Below 5%	No Additional Performance security
2	From 5% and above and below 10%	50% of (Difference between estimated cost put to tender and Bid Amount)
3	From 10% and above	150% of (Difference between estimated cost put to tender and Bid Amount)

Exact amount of Additional Performance Security (APS) in shape of Term Deposit Receipt pledged in favor of Block Development Officer, Beguniapada/ Bank Guarantee in favour of the Block Development Officer, Beguniapada from any Nationalized / Scheduled Bank in India counter guaranteed by its local branch at Bhubaneswar will be communicated through Letter of acceptance (LoA). After getting of (LoA) the successful bidder will produce the APS within 7 days of issue of letter of acceptance (LoA) by the Block Development Officer Beguniapada. If he/she fails, the bid shall be cancelled & he/she will be suspended for the time specified in the tender document. Further, proceeding for blacklisting shall be initiated against the bidder. If the APS is submitted in shape of Bank Guarantee by the bidder, then the validity of the Bank Guarantee should be for a minimum period equal to the period allowed for completion of the work plus defect liability period of one year and one month extra for transaction period.

36. Bid must be accompanied with scanned copies of valid Registration Certificate duly registered in CDMS portal, active GSTIN, PAN Card and Affidavit in support of their claim along with their bid failing which the bid will be rejected. Bidders registered as "Engineer Contractors" desirous to avail exemption of E.M.D for participating in bid shall have to produce an affidavit for not having availed this facility in three works during the year 2021-22. In such case, the successful Engineer Contractor has to produce the original Registration Certificate for recording the fact of availing exemption of E.M.D & ISD. for award of the work. Bidders registered as S.C. & S.T. Contractors desiring to avail concession(s) / price preference as per prevailing rules should upload necessary document and affidavit in support of their claim along with their bid, failing which their case may not be considered for availing price preference as per the above rule. No claim in this regard after opening of the bid will be entertained.

37. In case, if lottery is inevitable for finalization of the tender, then the tender accepting authority will finalize the tender through a transparent lottery system, which will be held in the office of the Block Development Officer, Beguniapada, Dist:- Ganjam. The date and time of the lottery will be intimated to the qualified bidders through their address given and Email ID/WhatsApp including office notice board.

38. The Block Development Officer, Beguniapada, Dist:- Ganjam may be contacted during office hours on any working days for any further clarification between 10:00 A.M to 5.00P.M.

Signature of Contractor


Block Development Officer,
Beguniapada

GENERAL SPECIFICATION

1. The tender should include supply of all materials, labour, tools and plants centering, shuttering, scaffolding etc. complete unless otherwise specified.
2. All materials other than Government supplied will have to be of approved quality. The decision of the Executive Engineer on this issue will be final.
3. All exposed iron work shall be painted two coat of priming by paints whose quality a shade has to be approved by the Executive Engineer.
4. Plastering on RCC work shall not be paid for, if done by the Contractor.
5. Before issue of the departmental materials to the Contactor shall furnish bank guarantee of any of the nationalized banks for a sum equal to the cost of the materials. The bank guarantee shall be valid for the entire period of the agreement. The same will be refunded to the Contractor only after , the materials supplied to him are fully utilized in the works and amount thereof recovered from his bills in full or if the materials are partly utilized , the unutilized materials are returned by him to the department in full and in good condition and receipt thereof duly acknowledged to the concerned departmental office.

SPECIAL CLAUSE

- a All stock and store materials like cement, steel, Maxphalt paints etc. are to be arranged and supplied by the contractor himself as per IS specification subjected to approval quality by the Engineer-in-charge.
- b No monetary claim or compensation of any kind what so ever will be entertained by the Department nor this can be termed as a plea by the Contractor to apply for extension of time to complete the work (This has been given effect from 01-04-1996

The machineries as and when required for execution of work should normally be arranged and supplied by the Contractor himself.

- c. No cement will be supplied by the department and the contractor has to procure cement of approved quality as specified in the agreement at his own arrangements and produce the cash vouchers in support there of in token of actual transaction without scope for reimbursement of extra cost involved if any.
- d. Payment will be made on receipt of bills in complete shape by the authority subject to availability of funds (Letter of Credit) under respective head of account. The department will not be liable for payment of any compensation for delay in payment of running / final bill. Nonpayment of bills due to contingency if any, during the course of execution of works shall not be treated as a bar for suspending the work.
- e. The work is to be completed within the stipulated period.

Signature of Contractor


Block Development Officer,
Beguniapada, Ganjam.

SECTION – 8
FORMS

AFFIDAVIT

I, Sri Aged years Son/ Daughter / Wife of Sri
..... at present residing at PO P.S.
Dist, Pin Do hereby solemnly affirm as follows.

- i. That, I possess a valid license for Execution of works contract issued by *..... Belongs to
..... Class & is valid up to **.....
- ii. I am submitting tenders before the Block Development Officer, Beguniapada for execution of the
work * “ **Renovation & Construction of CHC, Kodala,** ” in response to Tender Call Notice No.02/
2023-24. Date. 02.09.2023
- iii. I am swearing this affidavit that all tender documents and accompanying papers along with D.D (Non-
refundable) those being submitted by me before the **Block Development Officer, Beguniapada** are all
authentic and bonafied documents in the eyes of the law of the land.

That the facts stated in the affidavit are true to the best of my knowledge and belief.

Signature of Contractor

Note :

* Mention the license issuing authority.

** Mention the date up to which the license is valid.

*** Mention name of work for which tender is being submitted.


Block Development Officer
Beguniapada

PERFORMANCE RECORD OF CONTRACTOR


1. Name of the Contractor :
2. Registration No. and Date :
3. Class of Contractor :
4. Licensing Authority :
5. License valid up to :
6. Details of works executed :

Sl. No.	Jobs under execution	Agreement amount	Date of Commencement	Stipulated Date of Completion	Whether work is progressing as per programme	Reasons for delay, if any.
1	2	3	4	5	6	7

7. Whether the Contractor has requisite machineries & personnel deployed (details of machinery and personnel deployed) :
8. Whether the quality of construction is satisfactory :
9. Whether he has capability to make good the loss time :
10. Whether the Contractor has abandoned any work in the past three years, if yes, the details thereof. :
11. Whether the Contractor has entered in to any litigation in the past if yes, the details thereof. :

Name of the Certifying Officer
With official seal

Signature of Contractor


Block Development Officer
Beguniapada

Certificate of No relationship

I/We hereby certify that I/We am / are not related to any officer of P.W.D. of the rank of Asst. Engineer and above and any officer of the rank of Asst. Secretary and above in the P. R & D. W Deptt. I/ We am/are aware that if the facts subsequently proved to be false my/our contract will be rescinded with for feature of EMD & security deposit and I/We shall be liable to make good the loss or damage resulting from such cancellation.

I/We also note that, non-submission of this certificate will render my/ our tender liable for rejection.

Signature of Contractor

Address _____

Date: _____


**Block Development Officer,
Beguniapada**

ANNEXURE-"IV"

INFORMATION REGARDING CURRENT LITIGATION DEBARRING EXPELLING
OF TENDERER OR ABANDONMENT OF WORK BY THE TENDERER.


1. a) Is the tenderer currently involved in any litigation relating to the works. Yes/No
b) If yes, give details.
2. a) Has the tenderer or any of its constituent partners has been debarred / expelled by any agency in India during the last three years. Yes/No
3. a) Has the tenderer or any of its constituent partners failed to perform on any contract work in India during the last three years. Yes/No
b) If yes, give details :

Note:- If any information in this schedule is found to be incorrect or concealed, qualification application will be summarily be rejected.

Signature of Contractor

Address _____

Date: _____


Block Development Officer,
Beguniapada

BILL OF QUANTITIES

Name of the Work : Renovation & Construction of CHC Kodala.

MAIN GATE

SL. NO.	DESCRIPTION OF ITEM	QUANTITY	UNIT	RATE	AMOUNT
1	Earth work in excavation of foundation in all kinds of soil within 50m initial lead and 1.50m initial lift including rough dressing breaking clods to maximum 5cm to 7cm & laying in layers not exceeding .0.3m depth and as per direction of the Engineer-in-Charge	36.447	Cum	227.70	8298.98
2	Supplying & filling foundation and plinth with course sand well waiered and rammed including cost, cost of all labour, carriage, royalty, etc complete.	26.304	Cum	604.43	15898.93
3	C.C (1:4:8) with 4cm size HG CRUSHER BROKEN metal including all cost, conveyance,royalty & taxes etc.comp.to work site as per specification approved by the department & direction of E.I.C	3.617	Cum	4550.90	16460.61
4	Reinforced Cement concrete work of M-25 grade with 20mm & down grade black hard granite (Crusher broken) stone chips including hoisting & laying including cost, conveyance, taxes & royalty of all materials and labour with T&P etc. complete in all resoect.				
4.1	Foundation & Pedestal	6.659	Cum	6008.50	40010.60
4.2	Column pedestal to Plinth	1.955	Cum	13741.70	26865.02
4.3	Plinth	1.877	Cum	6826.31	12812.98
4.4	R.C.C. Column / Beam				
	Ground Floor	6.069	Cum	13741.70	83398.38
	Above 3 meter	0.927	Cum	15450.00	14322.15
4.5	R.C.C Roof Slab				
	Ground Floor	1.742	Cum	12367.40	21544.01
	Above 3 meter	2.072	Cum	13800.80	28595.26
4.6	R.C.C Chajja				
	Ground Floor	2.970	Sqm	1091.70	3242.35
4.7	LINTEL				
	Ground Floor	0.432	Cum	13022.60	5625.76
5	Supplying fitting & placing uncoated HYSD reinforcement including cutting, bendind, binding & placing the steel rods as per drawing & technical specification with cost of binding wire 18 to 20 gauge				
5.1	Ground Floor	26.810	qntl	9212.20	246979.08
5.2	First Floor	3.530	qntl	9237.83	32609.55
6	Brick work with Fly ash Bricks 23cm x 11cm x 8cm size having crushing strength not less than 75Kg/cm2 with dimensional tolerance ±2 percent in cement mortar (1:6) in Foundation and Plinth including watering curing, cost of carriage and royalty of all materials, cost of all labour, etc complete.				
	Ground Floor	4.396	Cum	4861.32	21372.31
6	Brick work with Fly ash Bricks 23cm x 11cm x 8cm size having crushing strength not less than 75Kg/cm2 with dimensional tolerance ±2 percent in cement mortar (1:6) in Superstructure including watering curing, cost of carriage and royalty of all materials, cost of all labour, etc complete.				
	Ground Floor	8.527	Cum	4894.65	41736.68
	Above 3 meter	5.170	Cum	5182.33	26792.66
7	12mm thick C.P.(1:6) on brick masonry to the smooth surface including watering, curing, cost, carriage, royalty of all materials, cost of all labour, etc complete as per the direction of E.I.C.				

			28.914	Sqm	149.83	4332.18
		Ground Floor				
8		16mm thick C.P. (1:6) over brick masonry to the smooth surface including watering, curing cost, carriage, royalty, and taxes of all materials, cost of all labour, etc complete as per the direction of E.I.C.	77.112	Sqm	214.26	16522.02
		Ground Floor Qty	59.614	Sqm	219.57	13089.31
		above 3 meter				
9		6 mm thick C.P. (1:4) to RCC surfaces finished smooth including closed deep chiping and slury treatment , watering, curing cost, carriage & royalty of all materials, cost of all labour, etc complete as per the direction of E.I.C.	11.288	Sqm	166.57	1880.24
		Ground Floor Qty.	10.300	Sqm	170.73	1758.57
		above 3 meter				
10		Supplying, fitting and fixing tile in floors of approved make conformaing to IS:13755 laid on 20 mm thick cement mortar (1:4) and filling joints with white cement of approved quality including cost of all materials, etc. required for the work all complete as per direction of E.I.C.				
10.1		S/F/F of vified floor tiles of premium grade having thickness 8mm to 10mm (60cm x 60cm plain / ivory)	11.288	Sqm	1069.96	12077.71
		Ground Floor Qty.				
11		Fixing tiles in skirting and risers of steps on 12mm thick CP (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the tiles including cost, carriage, cost of all labour etc. complete.				
11.1		Granite	4.008	Sqm	2184.97	8757.36
		Ground Floor				
12		Fixing tiles in dados on 12mm thick CP (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the tiles including cost, carriage, cost of all labour etc. complete.				
12.1		Ceramic Tiles	1.740	Sqm	888.47	1545.94
		Ground Floor				
12.2		Ceramic wall tile	28.800	Sqm	888.47	25587.94
		Ground Floor	13.152	Sqm	904.32	11893.58
		above 3 meter				
13		Water Proofing cement Paint two coat				
		Ground Floor	28.914	Sqm	37.55	1085.72
14		Finishing wall surface with two coat of Cement based wall putty (water based) of approved make and finished smooth & even surface to receive painting including cost of scaffolding etc. with cost of all materials, labour etc. complete.				
		Ground Floor	117.314	Sqm	77.53	9095.35
		First Floor	56.762	Sqm	79.08	4488.77
15		Painting work				
15.1		Priming walls with water bound cement primer of approved shade on new wall surface to give an even shade including cost of primer. (inner , outer and ceiling)				
		Ground Floor	117.314	Sqm	65.95	7736.86
		First Floor	56.762	Sqm	67.53	3832.95
15.2		Wall painting 2 coats with plastic emulsion paint of approved shade on new work to give an even shade including cost of paint. (inner wall)				
		Ground Floor	40.202	Sqm	88.17	3544.61
		First Floor	10.300	Sqm	89.87	925.70
15.3		Wall painting 2 coats with weather coat paint of approved shade on old work to give an even shade including cost of paint including all cost conveyance royalties taxes etc complete. (Outer wall)				

	Ground Floor				
	First Floor	77 112	Sqm	81.28	6267 66
	Proposed Door, Flush Door 35 mm thick	46 462	Sqm	82.99	3855 68
16		1 917	Sqm	8656 00	16593 55
17	Supplying and fitting fixing of Un-plasticised Poly vinyl chloride (UPVC) (FENESTA / NCL VEKA LTD) Three Track - Three Panel sliding window - 60 series duly manufactured using UPVC reinforced profiles of 108 mm X 45mm X 2.5mm for outer frames and window sash of 39mm X 58mm X 2.5mm capable of mounting single glazing system, structurally reinforced with hot dip galvanized up to 50 microns of minimum thickness of 1.5 mm prefabricated and welded through fusion welding the window, frame shall be fitted with 6 mm thick clear toughened glass of SAINTE - GOBAIN make duly fixed with EPDM weathering seal resistant and the system is to be installed using Reinforced Large Coupler at the site using anchor fasteners, silicon rubber sealant, easy glazing/ deglazing at site etc. including cost and conveyance of all materials, accessories, labour charges, materials and product conforming to ASTM D 638-14, EN-477-95 and other applicable codes and standards.				
	Window	4.320	Sqm	5984.00	25850 88
17.1	WPC (Wood polymer Composite) Choukhat (Size 50x125mm)	4.800	Rmt.	1015.00	4872 00
18	Supplying of M.S Gate, steel window and door, M.S window grills to openings and collapsible gate of approved specification and approved quality with cost, conveyance, royalties and taxes of all materials, all labour and T&P required for the work etc. complete in all respect as per the direction of Engineer-in-charge.	83.635	kg	80.28	6714.23
20	Supplying of M.S Gate, steel window and door, M.S window grills to openings and collapsible gate of approved specification and approved quality with cost, conveyance, royalties and taxes of all materials, all labour and T&P required for the work etc. complete in all respect as per the direction of Engineer-in-charge.	596.440	kg	80.28	47882.20
21	Painting two coats with any approved paint over a coat of priming to new iron work including cost of the primer and paint sand papering polishing the surface with cost conveyance of all materials, labour and labour cess with T&P required for the work etc complete in all respect as per direction of the Engineer-in-charge.	19.020	SQM	201.84	3839.00
TOILET NEAR LAB					890595.32
1	Earth Work in exavation				
1.1	Earth Work in exavation of foundation in ordinary soil within initial leads of 50m & lifts of 1.5m including dressing and levelling of bed etc. and adding contractor's profit and over head charges, etc. complete in all respect	27.750	Cum	153.88	4270 05
2	Supplying & filling foundation and plinth with course sand well watered and rammed including cost, cost of all labour, carriage, royalty, etc complete.	31.221	Cum	604.43	18870.91
3	C.C (1:4:8) with 4cm size HG CRUSHER BROKEN metal including all cost, conveyance, royalty & taxes etc.comp.to work site as per specification approved by the department & direction of E.I.C	6.314	Cum	4550.90	28734.38
4	R.C.C. work of m-25 using 20mm and down graded hard granite Crusher broken chips including laying, hoisting, Centring & shuttering with all cost, conveyance etc. complete.				
4.1	Foundation & Pedestal	2.813	Cum	6008.50	16901 91
4.2	Column pedestal to Plinth	0.498	Cum	13741.70	6843 37
4.3	Plinth	1.929	Cum	6826.31	13167 94

4.4	R C C Column / Beam	2.304	Cum	13741.70	31990.88
	Ground Floor				
4.5	R C C Roof Slab	3.705	Cum	12367.40	45821.72
	Ground Floor				
4.6	Chajja	4.406	Sqm	1091.70	4810.62
	Ground Floor				
4.7	LINTEL	0.831	Cum	13022.60	10821.78
	Ground Floor				
5	Supplying fitting & placing uncoated HYSD reinforcement including cutting, bending, binding & placing the steel rods as per drawing & technical specification with cost of binding wire 18 to 20 gauge				
5.1	Ground Floor	15.400	qntl	9212.20	141867.88
6	Brick work with Fly ash Bricks 23cm x 11cm x 8cm size having crushing strength not less than 75Kg/cm ² with dimensional tolerance ± 2 percent in cement mortar (1:6) in Foundation and Plinth including watering curing, cost of carriage and royalty of all materials, cost of all labour, etc complete.				
6.1	Ground Floor	9.832	Cum	4861.32	47796.50
6	Brick work with Fly ash Bricks 23cm x 11cm x 8cm size having crushing strength not less than 75Kg/cm ² with dimensional tolerance ± 2 percent in cement mortar (1:6) in Superstructure including watering curing, cost of carriage and royalty of all materials, cost of all labour, etc complete.				
6.1	Ground Floor	14.078	Cum	4894.65	68906.88
7	12mm thick C.P.(1:6) on brick masonry to the smooth surface including watering, curing, cost, carriage, royalty of all materials, cost of all labour, etc complete as per the direction of E.I.C.				
	Ground Floor	101.178	Sqm	149.83	15159.50
8	16mm thick C.P. (1:6) over brick masonry to the smooth surface including watering, curing cost, carriage, royalty, and taxes of all materials, cost of all labour, etc complete as per the direction of E.I.C.				
	Ground Floor Qty.	72.720	Sqm	214.26	15580.99
9	6 mm thick C.P. (1:4) to RCC surfaces finished smooth including closed deep chipping and slury treatment , watering, curing cost, carriage & royalty of all materials, cost of all labour, etc complete as per the direction of E.I.C.				
	Ground Floor Qty.	26.360	Sqm	166.57	4390.80
10	Supplying, fitting and fixing tile in floors of approved make conformaing to IS:13755 laid on 20 mm thick cement mortar (1:4) and filling joints with white cement of approved quality including cost of all materials, etc. required for the work all complete as per direction of E.I.C.				
10.1	S/F/F of ceramic floor tiles of premium grade having thickness 7mm to 8mm (30cm x 30cm / 40cm x 40cm special plain / printed series)				
	Ground Floor Qty.	22.427	Sqm	919.24	20615.70
11	Fixing tiles in skirting and risers of steps on 12mm thick CP (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the tiles including cost, carriage, cost of all labour etc. complete.				
11.1	Granite (Above 0.10 to 0.40 Sqm.)				
	Ground Floor	18.231	Sqm	2184.97	39835.06
12	Fixing tiles in dados on 12mm thick CP (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the tiles including cost, carriage, cost of all labour etc. complete.				
12.1	Ceramic Tiles				

	Ground Floor	96.120	Sqm	888.47	85399.74
14	Finishing wall surface with two coat of Cement based wall putty (water based) of approved make and finished smooth & even surface to receive painting including cost of scaffolding etc. with cost of all materials, labour etc. complete.				
	Ground Floor	200.258	Sqm	77.53	15526.01
15	Paint work				
15.1	Priming walls with water bound cement primer of approved shade on new wall surface to give an even shade including cost of primer. (inner , outer and ceiling)				
	Ground Floor	200.258	Sqm	65.95	13207.02
15.2	Wall painting 2 coats with plastic emulsion paint of approved shade on new work to give an even shade including cost of paint. (inner wall)				
	Ground Floor	101.178	Sqm	88.17	8920.86
15.3	Wall painting 2 coats with weather coat paint of approved shade on old work to give an even shade including cost of paint including all cost conveyance royalties taxes etc complete. (Outer wall)				
	Ground Floor	72.720	SQM	81.28	5910.68
16	Providing fitting fixing of approved make 35mm thick (Laminated Finished) factory made Flush Doors, of different sizes finished with 1mm thick laminate of approved shade and colour to both sides fixed to teak wood beading/ liping as per the design, wherever necessary the glazing portion of the door will be made out of 6mm thick glass with itching as required to be fixed with 50x18mm /48x24mm teak beading finished with melamine polish / 1mm thick laminate.. The glass jointing shall be tightened with silicon or approved jointing material for proper rigidity. The door shall be provided with all necessary fittings and fixtures, i.e Godrej Ultra Veritibolt Lock (Model 1 CK) ,125x75x3 mm SS204 Hinges, approved make Door closer,Door Stoper etc with all accessories, labour T&P etc complete.	5.176	Sqm	8656.00	44802.59
16.2		0.540	Sqm	6414.47	3463.81
17	Supply, fitting & fixing of WPC Choukat with size of 4"x2.5" of saburi/amulya/ecoste branded make. The cost includes choukat, labour, accessories etc all complete	15.840	Rmt.	1015.00	16077.60
18	Supplying, fitting and fixing of stainless steel of 304 grade in hand railing using 50mm dia of 32mm x 32mm x 2mm @ 0.90mtr C/C and stainless square pipe bracing of size 32mm x 32mm x 2mm 3 rows in staircase as per approved design and specification, buffing, polishing etc with cost, conveyance, taxes of all materials, labour, T & P etc required for the work complete in all respect. (Data for 3.26 sqm.)	5.000	Rmt.	3518.57	17592.85
TOILET ATTACHED TO INTIGRATED LAB					746956.94
1	Earth Work in exavation				
1.1	Earth Work in exavation of foundation in ordinary soil within initial leads of 50m & lifts of 1.5m including dressing and levelling of bed etc. and adding contractor's profit and over head charges, etc. complete in all respect	14.312	Cum	153.88	2202.27
2	Supplying & filling foundation and plinth with course sand well watered and rammed including cost, cost of all labour, carriage, royalty, etc complete.	10.655	Cum	604.43	6440.20
3	C.C (1:4:8) with 4cm size HG CRUSHER BROKEN metal including all cost, conveyance,royalty & taxes etc.comp.to work site as per specification approved by the department & direction of E.I.C	1.868	Cum	4550.90	8501.08
4	R.C.C. work of M-25 using 20mm and down graded hard granite Crusher broken chips including laying, hoisting, Centring & shuttering with all cost, conveyance etc. complete.				

4.1	Foundation & Pedestal	1.757	Cum	6008.50	10556.93
4.2	Column pedestal to Plinth	0.269	Cum	13741.70	3696.52
4.3	Plinth	0.841	Cum	6826.31	5740.92
4.4	R.C.C. Column / Beam Ground Floor	1.376	Cum	13741.70	18908.58
4.5	R.C.C Roof Slab Ground Floor	0.711	Cum	12367.40	8793.22
4.6	LINTEL Ground Floor	0.420	Cum	13022.60	5469.49
5	Supplying fitting & placing uncoated HYSD reinforcement including cutting, bending, binding & placing the steel rods as per drawing & technical specification with cost of binding wire 18 to 20 gauge				
5.1	Ground Floor	7.300	qntl	9212.20	67249.06
6	Brick work with Fly ash Bricks 23cm x 11cm x 8cm size having crushing strength not less than 75Kg/cm ² with dimensional tolerance ± 2 percent in cement mortar (1:6) in Foundation and Plinth including watering curing, cost of carriage and royalty of all materials, cost of all labour, etc complete.				
6.1	Ground Floor	2.900	Cum	4861.32	14097.83
6	Brick work with Fly ash Bricks 23cm x 11cm x 8cm size having crushing strength not less than 75Kg/cm ² with dimensional tolerance ± 2 percent in cement mortar (1:6) in Superstructure including watering curing, cost of carriage and royalty of all materials, cost of all labour, etc complete.				
6.1	Ground Floor	7.130	Cum	4894.65	34898.85
7	12mm thick C.P.(1:6) on brick masonry to the smooth surface including watering, curing, cost, carriage, royalty of all materials, cost of all labour, etc complete as per the direction of E.I.C.				
	Ground Floor	39.009	Sqm	149.83	5844.72
8	16mm thick C.P. (1:6) over brick masonry to the smooth surface including watering, curing cost, carriage, royalty, and taxes of all materials, cost of all labour, etc complete as per the direction of E.I.C.				
	Ground Floor Qty.	24.552	Sqm	214.26	5260.51
9	6 mm thick C.P. (1:4) to RCC surfaces finished smooth including closed deep chipping and slury treatment , watering, curing cost, carriage & royalty of all materials, cost of all labour, etc complete as per the direction of E.I.C.				
	Ground Floor Qty.	5.684	Sqm	166.57	946.78
10	Supplying, fitting and fixing tile in floors of approved make conforming to IS:13755 laid on 20 mm thick cement mortar (1:4) and filling joints with white cement of approved quality including cost of all materials, etc. required for the work all complete as per direction of E.I.C.				
10.1	Ceramic Floor Tile (30x30 / 40x40cm) Ground Floor Qty.	5.684	Sqm	919.24	5224.96
11	Tiles in Daddo Ceramic Wall Tile (20x30 / 20x20cm) in daddo Ground Floor Qty.	45.000	Sqm	888.47	39981.15
13	Finishing wall surface with two coat of Cement based wall putty (water based) of approved make and finished smooth & even surface to receive painting including cost of scaffolding etc. with cost of all materials, labour etc. complete. Ground Floor	69.245	Sqm	77.53	5368.56

14	Paint work				
14.1	Wall Priming one coat. (inner, outer & ceiling paint area) Ground Floor	69.245	Sqm	65.95	4566.71
14.2	Wall painting 2 coats with plastic emulsion paint of approved shade on new work to give an even shade including cost of paint. (inner area paint) Ground Floor	44.693	Sqm	88.17	3940.58
14.3	Wall painting 2 coats with weather coat paint of approved shade on new work to give an even shade including cost of paint. (outer area paint) Ground Floor	24.552	Sqm	81.28	1995.59
15	Providing fitting fixing of approved make 35mm thick (Laminated Finished) factory made Flush Doors, of different sizes finished with 1mm thick laminate of approved shade and colour to both sides fixed to teak wood beading/ liping as per the design, wherever necessary the glazing portion of the door will be made out of 6mm thick glass with itiching as required to be fixed with 50x18mm /48x24mm teak beading finished with melamine polish / 1mm thick laminate.. The glass jointing shall be tightened with silicon or approved jointing material for proper rigidity. The door shall be provided with all necessary fittings and fixtures, i.e Godrej Ultra Veritibolt Lock (Model 1 CK) ,125x75x3 mm SS204 Hinges, approved make Door closer,Door Stoper etc with all accessories, labour T&P etc complete.	5.112	Sqm	8656.00	44249.47
15.2	ventilation	0.270	Sqm	6414.47	1731.91
16	Supply, fitting & fixing of WPC Choukat with size of 4"x"2.5" of saburi/amulya/ecoste branded make. The cost includes choukat, labour, accessories etc all complete	11.400	rmt	1015.00	11571.00
17	MS Grill for window	5.227	kg	80.28	419.62
18	Supplying, fitting and fixing of stainless steel of 304 grade in hand railling using 50mm dia of 32mm x 32mm x 2mm @ 0.90mtr C/C and stainless square pipe bracing of size 32mm x 32mm x 2mm 3 rows in staircase as per approved design and specification, buffing, polishing etc with cost, conveyance, taxes of all materials, labour, T & P etc required for the work complete in all respect. (Data for 3.26 sqm.)	4.000	rmt	3518.57	14074.28
PARKING & LANDSCAPING					331730.79
1	Earth Work in exavation				
1.1	Earth work in all kinds of soil within 50m. Initial lead and 1.5m. Initial lift including rough dressing and breaking clods to maximum 5cm.to 7cm. and laying in layers not exceeding 0.3 m. in depth asper direction of the Engineer-in-charge.	18.500	Cum	227.70	4212.45
1.2	Earthwork in stoney earth	21.600	Cum	322.47	6965.25
2	Supplying & filling foundation and plinth with course sand well watered and rammed including cost, cost of all labour, carriage, royalty, etc complete.	22.143	Cum	604.43	13383.89
3	C.C. (1:2:4) with 12mm chips	15.600	Cum	6562.44	102374.06

4	<p>Providing, lifting, hoisting and laying cement concrete of M-25 grade as per approved designs and drawings having a minimum compressive strength (in work test) 25 Kg. / Square cm. in 15 cm. cubes at 28 days after mixing and test conducted in accordance with I.S. 516 using 12 mm. to 20 mm. size black hard crushed broken granite stone chips and screened and washed sharp sand for mortar of approved quality from approved quarry, washed and cleaned (20mm. size chips not to exceeds 25 %) to be mixed in concrete mixture with Portland slag cement (PSC) including hoisting, lowering, laying and compaction concrete by using vibrators, watering and curing for 28 days, centering and shuttering then after dismantling and removing debris from the work site and finishing the exposed surface smooth providing grooves or beads wherever necessary including cost, conveyance, loading, unloading, royalties and taxes of all materials and cost of all labours, sundries, T & P required of the work etc. complete in all respect as directed by the Engineer-in-Charge.</p>				
	Kerb Stone	13.500	cum	6826.31	92155.13
5	<p>Providing and laying 80 mm thick factory made cement concrete interlocking paver block of M-40 grade made by block making machine with strong vibratory compaction of approved size, design & shape, laid in required colour and pattern over and including 75mm thick sand filling as per drawing, specification and direction of Engineer-In-charge. Red, Yellow or approved colour.</p>				
	Paver block	271.933	Sqm	922.07	250740.96
6	<p>Supplying and stacking of good earth at site including royalty and carriage upto 5 km complete (earth measured in stacks will be reduced by 20% for payment).ncluding cost of labour, T&P, all taxes and royalties etc. complete as directed by engineer-in-charge</p>	136.050	Cum	314.75	42821.74
7	<p>Providing and laying Neelgiri/Mexican grass turf with earth 50mm to 60mm thickness of existing ground prepared with proper level and ramming with tools wooden (Dhurmos) and than rolling the surface with light roller make the surface smoothen and light watering with sprinkler and maintenance for 30 days or more till the grass establish properly, as per direction of officer-in-charge. CPWD DSR CH-1 NEW 2.33 LANDSCAPE</p>	907.000	Sqm	211.25	191603.75
8	<p>Supply, fitting & installation of Mission Shakti café kiosk with all materials, furnitures and fixtures. Rate as approved by DRDA-ganjam</p>	1.000	No.	483569.00	483569.00
9	<p>Supplying, fitting and fixing of stainless steel of 304 grade in hand railing using 50mm dia of 32mm x 32mm x 2mm @ 0.90mtr C/C and stainless square pipe bracing of size 32mm x 32mm x 2mm 3 rows in staircase as per approved design and specification, buffing, polishing etc with cost, conveyance, taxes of all materials, labour, T & P etc required for the work complete in all respect. (Data for 3.26 sqm.)</p>	20.000	Rmt.	3518.57	70371.40
1	<p>Earthwork in excavation in all types of soil for site leveling, foundation, pits, trenches and other civil works upto and including 1.5metre lift and stacking the soil upto a lead of 100 metre and including dewatering, removing slush, shoring and strutting (as required), complete as per specification and as directed by the Engineer-In-Charge.</p> <p>a) All kinds of soil.</p> <p>b) Stoney Earth.</p>				
RAINWATER HARVESTING.					

1	Earthwork in excavation in all types of soil for site leveling, foundation, pits, trenches and other civil works upto and including 1.5 metre lift and stacking the soil upto a lead of 100 metre and including dewatering, removing slush, shoring and strutting (as required), complete as per specification and as directed by the Engineer-In-Charge.				
a)	All kinds of soil.	Cum	52.5	227.70	11954.25
b)	Stoney Earth.	Cum	21	322.47	6771.77
2	Supplying, filling, spreading & leveling stone boulders of size range 50mm to 200mm, in recharge pit, in the required thickness, for all leads & lifts, all complete as direction of Engineer-In-Charge.	Cum	10.125	1850.00	18731.25
3	Supplying, filling, spreading & leveling gravels of size range 5mm to 10mm, in recharge pit, over the existing layar of boulders, in the required thickness, for all leads & lifts, all complete as direction of Engineer-In-Charge.	Cum	10.125	2150.00	21768.75
4	Supplying, filling, spreading & leveling coarse sand of size range 1.5mm to 2mm, in recharge pit, over the existing layar of gravels layer, in the required thickness, for all leads & lifts, all complete as direction of Engineer-In-Charge.	Cum	10.125	3500.00	35437.50
5	Providing, laying and compacting plain cement concrete of grades (1:4:8) as defined in IS:456 with graded stone aggregates at all heights and depths, below finished ground level including curing all materials, tools, labour complete as per specifications and directions of the Engineer-In-Charge.	Cum	1.5	4550.90	6826.35
6	Providing, lifting, hoisting and laying Reinforced cement concrete of M-25 grade as per approved designs and drawings having a minimum compressive strength (in work test) 25 Kg. / Square cm. in 15 cm. cubes at 28 days after mixing and test conducted in accordance with I.S. 516 using 12 mm. to 20 mm. size black hard crushed broken granite stone chips and screened and washed sharp sand for mortar of approved quality from approved quarry, washed and cleaned (20mm. size chips not to exceeds 25%) to be mixed in concrete mixture with Portland slag cement (PSC) including hoisting, lowering, laying and compaction concrete by using vibrators, watering and curing for 28 days, centering and shuttering then after dismantling and removing debris from the work site and finishing the exposed surface smooth providing grooves or beads wherever necessary including cost, conveyance, loading, unloading, royalties and taxes of all materials and cost of all labours, sundries, T & P required of the work etc. complete in all respect as directed by the Engineer-in-Charge. But excluding cost and conveyance of M.S. rods or Tor steel and binding wires and labour charges for straightening, cutting, bending etc. of M.S. rods	Cum	3.75	6008.50	22531.88
7	Supplying, straightening, cutting, bending, placing in position and binding reinforcement steel work in RCC/reinforced brick works as per drawing and specification including preparation of respective bar bending schedule etc. all complete as per direction of EIC.				
	Cold Twisted bars, Thermo-Mechanically-treated bars.	Qntl	3.4875	9212.20	32127.55
8	Providing and constructing brick work using Fly Ash bricks in cement sand mortar (1:4) in foundations and superstructures, sewer, drains etc. bonding, lining, levelling, plumbing, racking out joints, curing as per specifications, all materials, tools and labour complete.	Cum	45.675	4894.65	223563.14

9	Boring/drilling bore well of required dia for casing/strainer pipe by suitable method prescribed in IS; 2800 (part-1), including collecting samples from different strata, preparing and submitting strata chart/bore log, including hire & running charges of all equipments, tools, plants & machineries required for the job, all complete as per direction of Engineer-In-Charge, up to 90 metre depth below ground level. a) All kinds of soil 300mm dia.	Mtr	100	772.60	77260.00
10	Supplying, assembling, lowering and fixing in vertical position in bore well Unplasticized PVC medium well screen (RMS) pipes with ribs, conforming to IS : 12818, including hire & labour charges, fittings & accessories etc. all complete, for all depth, as per direction of Engineer-In-Charge. a) 200mm nominal size dia.	Mtr	120	1309.05	157086.00

614058.43

CHILDREN'S PLAY EQUIPMENT.

Supplying, Installation, Testing and Commissioning of Following Children's Play Equipment as per mentioned Product details from Flora Fountains and Amusements or approved Equivalent with Body of FRP and Structure of GI of specified Dia/size and wall thickness not less than 2.0mm, etc. complete as per Technical Datasheet, Indian Standard Code and as Directed By Engineer-in-charge or Project Architect.

1	SPRING RIDER:- Duck/Donald/Mickey/Fish, Area-1'x2', Height-1'-6"	Nos	1.00	10900	10900
2	DELUXE SPRING RIDER:- Duck/Sea Horse/Mickey/Fish, Area-1'x2', Height-1'-6", Age group-2-5 years	Nos	1.00	14900.00	14900.00
3	ROCKING BOAT:- Area-1'x5', Safe Area-3'x7', Height-18", Age group-2-6 years, Seat-FRP, Pipe- 25 mm, 20mm & 15mm ID G.I Medium Pipe.	Nos	1.00	10900.00	10900.00
4	THREE-IN-ONE - (SEA-SAW-01, SWING-01, SLIDE-01):- Area-7'x12', Safe Area-8'x12', Height-3'-6", Age group-2-6 years, Seat-FRP, Pipe- 40 mm, 25mm & 15mm ID G.I Medium Pipe.	Nos	1.00	68000.00	68000.00
5	SPRING SEA SAW (FOUR-SEATER) :- Area-2'x10', Safe Area-4'x14', Height-24", Age group-2-10 years, Seat-Plastic, Pipe- Main Pipe 10 Length of 65mm ID G.I Pipe, Handle- 25mm & 20mm ID G.I Pipe. Medium Pipe.	Nos	1.00	29900.00	29900.00
6	ARCH SWING:- Area-4'x10', Safe Area-4'x10', Height-7', Age group-3-14 years, Seat-02 no Rubber Seat, Main Pipe- 65mm ID B-Class G.I Pipe, Top Pipe- 50mm ID B-Class G.I Pipe, Chain- 8mm SS Chain Rubber Coated.	Nos	1.00	36000.00	36000.00
7	ROTO CURVE SLIDE. :- Area-4'x16', Safe Area-7'x20', Height-7', Age group-3-14 years, Slide-Roto Mould, Pipe-Deck Pipe: 65mm ID B-Class GI Pipe, Grill- 20mm ID B-Class GI Pipe, Ladder-25mm ID B-Class GI Pipe, Step- 16-gauge MS Sheet, Handle-20mm ID B-Class GI Pipe.	Nos	1.00	75000.00	75000.00

(Rupees

Asst. Exe
Be

Medical Equipment

1	Supply, fixing, fitting of Hospital Semi Fowler Beds with Pretreated & Epoxy Powder Coated. With Size 2010x910x600 mm. ABS moulded head and foot panel with locking. PP Head and Foot Panels with metal inserts along with lock and corner buffer. Urine Bag Holder on Both Sides. The cost includes, materials, labour, T&P etc complete	No.	28	19246.00	538888.00
2	Supply, hanging, fitting and fixing of hospital bed curtain tracks, channels and curtains with all accessories. The cost includes all Rft materials, accessories, labour T&P etc complete.	Rft	769.16	464.00	356890.24
3	Supply, fixing & fitting of ELECTRIC FULL FOWLER HOSPITAL BED WITH STEEL RAILING REMOTE OPERATED. Collapsible Side Railings.-Sections Perforated CRC Sheet. ABS moulded head and foot panel with locking. PP Head and Foot Panels with metal inserts along with lock and corner buffer. Urine Bag Holder on Both Sides.	No.	4	38154.00	152616.00
				Total	245600.00

My / Ou

4	Supply, fixing, fitting of automatic labour delivery bed. Overall size 1880Lx660Wx600-800H cms.S.S telescopic IV Rod with 4 hooks Tubularframe mounted on 125mm central locking castor.ABS head panel & S.S tray. Leg end section can slide under the main section. Height adjustment through high quality hydraulic pump. Back section adjustment through rack mechanism. Pretreated epoxy powder coated framework. Cost includes all etc	No.	2	85936.00	171872.00
5	Supply, fixing, fitting of patient examination table. 1870 L x 560 W x 810 H (IN MM) in size. Made of pretreated epoxy powder coated table. Provided With 3 Drawers And 3 Utility Cabinet. Provision for BP aparatus. Etc complete	No.	7	21450.00	150150.00
6	Supply, Installation, testing and commissioning of electronic based surgery OT bed with hydraulic system. Stainless steel made. Cost includes, table, labour T&P etc	No.	1	77120.00	77120.00
7	WAITING 3-SEATER CHAIR :- providing and fixing S.S Waiting 3 seater chair or similar to model or equivalent make including materials, labour, taxes etc as per approved design & instruction of Architect/ Engineer-In-Charge.	Nos	18	12500.00	225000.00
8	CORNER GUARD.	Rmt	15	1575.00	23625.00
9	Supply, fitting,fixing of high back revolving netted cusioned chairs of branded make of featurelite/nilkamal/rashmi/godrej make. Cost includes all etc complete	No.	8	11200.00	89600.00
10	Supply, fitting,fixing of Medium back revolving netted cusioned visitor chairs of branded make of featurelite/nilkamal/rashmi/godrej make. Cost includes all etc complete	No.	25	5600.00	140000.00
11	Supply, fitting,fixing of 300mm dia stainless steel round chairs. Cost includes all etc complete	No.	12	2500.00	30000.00
				Total	1955761.24
				Net Total	6042900.35
				Say	6042900.00

(Rupees Sixty Lakhs forty Two Thousand Nine Hundred Only)

Approved


Executive Engineer
Beguniapada


Block Development Officer
Beguniapada

Our quoted rate is

(figures and words) excess over /less than / equal to the above estimated cost .

%(both in

Signature of Tenderer

ANNEXURE-"VI"

CHECK LIST (SUBMITTED OR NOT)

		Tick appropriate column			
1	Certificate of Registration of Contractor with enrolment in CDMS Portal-attached.	YES		NO	
2	Certified copy of power of attorney in case of partnership firm, limited or corporation attached.	YES		NO	
3	Bid security declaration furnished.	YES		NO	
4	Copy of PAN Card Furnished.	YES		NO	
5	Copy of GST number with related documents furnished.	YES		NO	
6	Affidavit for authenticity of documents, Bid security declaration in lieu of EMD & Bid information furnished.	YES		NO	
7	Cost of bid document + GST number with related documents	YES		NO	
8	List of Plant / Equipment Furnished	YES		NO	
9	No Relation Certificate	YES		NO	
10	Affidavit for during the year (for Engineering Contractors)	YES		NO	
11	No Litigation Certificate	YES		NO	
12	Any other document as per DTCN.	YES		NO	
a		YES		NO	
b		YES		NO	
c		YES		NO	


 Block Development Officer,
 Beguniapada